Bill of Quantities (BOQ)

Upgrading of Kabikesari Motarmarga, Bhanu-03, Tanahun

IFB No.: 3370138034/IDO/TANAHUN/NCB/W/06/083-084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss of damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as per Contract Document [GCC 19]	PS	1.00	22,000.00 Twenty-two thousand rupees only.	22,000.00 Twenty-two thousand rupees only.
	Total provisional sums				22,000.00 Twenty-two thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer. [SSRBW Clause 110]	Nos.	1.00			
1.2	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. [SSRBW Clause 907]	Cum	180.91			
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. [SSRBW Cause 3111]	Cum	77.75			
1.4	Providing and laying of Plain/Reinforced Cement Concrete M15 in foundation complete as per drawing and technical specifications (including Forms works). (SSRBW Cause 2000)	Cum	2.69			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Providing and laying stone masonry work in cement mortar 1:4 in structure complete as Including Weephole and backfilling per drawing and technical specifications (Random Rubble Masonry) . (SSRBW Clause 2602,2603 2607)	Cum	42.03			
1.6	Providing and Laying Reinforced Cement Concrete Flush jointed Pipe for culverts Providing and Laying Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing cement mortar 1:2 as per Drawing and Technical Specifications.(600mm)	Rm	7.50			
1.7	Providing and laying of Reinforced Cement Concrete in Superstructure complete as per Drawing and Technical Specifications. Grade M20(Including Formwork) (SSRBW Cause 2000)	Cum	72.37			
1.8	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications. [SSRBW-2014]	Kg	2,979.93			

Total Item Price	
VAT (13.00%)	
Grand Total	