Bill of Quantities (BOQ)

Construction & Upgrading of Road, Drain and other structures of Rudra Path to south-east road and Sanchar Griha Path of Ward no. 12.

IFB No.: 801054805/SNP/NCB-10/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Providing and installation of Project Signboards,Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property, Carry out additional tests for material and works,Dismantling of the existing structures (Drain, etc,), Relocation of the utilities (water supply, telephone, etc,) and services,dewatering and other necessary works as instructed by the Engineer as per approved Norms and Technical Specifications.	PS	1.00	35,000.00 Thirty-five thousand rupees only.	35,000.00 Thirty-five thousand rupees only.
	Total provisional sums				35,000.00 Thirty-five thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications. [Mechanical Means]	Sqm.	906.52			
1.2	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications. [Mechanical Means]	Cum.	90.652			
1.3	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. [RCC grade M20]	Cum.	135.978			
1.4	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications	Kg	4,559.62963			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Centering and shuttering with wooden/ metal for all kinds of R.C.C. work including all necessary propping, scaffolding, staging, supporting, dismantling and clearing from the site, etc. all complete as per design drawings, specifications and instruction of the site engineer .	Sqm.	97.86			

Total Item Price	
VAT (13.00%)	
Grand Total	