Bill of Quantities (BOQ)

Upgrading and Construction of different roads at Ward no. 06.

IFB No.: 801054805/SNP/NCB-12/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Providing and installation of Project Signboards,Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property, Carry out additional tests for material and works,Dismantling of the existing structures (Drain, etc,), Relocation of the utilities (water supply, telephone, etc,) and services,dewatering and other necessary works as instructed by the Engineer as per approved Norms and Technical Specifications.	Ps	1.00	63,000.00 Sixty-three thousand rupees only.	63,000.00 Sixty-three thousand rupees only.
	Total provisional sums				63,000.00 Sixty-three thousand rupees only.

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Clearing grass/top soil and removal up to a distance of 50 meters outside the periphery of the area, including cutting and filling of small undulation. [Manual Means]	Sq.m	2,133.63			
1.2	Road way excavation in all types of soil including removal of stumps and other deleterious matter and disposal upto relevant lift and lead all complete as per drawing and technical specification. [Mechanical Mean]	Cu.m	192.67			
1.3	Providing & laying boulder stone soling in foundation & floor including voids filling with sand all complete as per instruction of the site engineer.	Cu.m	65.18			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying of Plain / Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. [PCC grade M10]	Cu.m	16.72			
1.5	Providing and laying of Plain / Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. [PCC grade M15]	Cu.m	24.42			
1.6	Providing and laying Brick Masonry Work in Cement mortar in Foundation / structure complete excluding Pointing and Plastering, as per Drawing and Technical Specifications. [CS Mortar 1:4]	Cu.m	44.80			
1.7	Providing and applying 12.5 mm thick Plaster with cement mortar on brick work structure as per Technical Specifications. [CS Mortar 1:4]	Sq.m	307.36			
1.8	3 mm thick cement sand punning on floor, skriting, dado etc, including mixing laying and rubbing with steel trowel to a hard, smooth and shining surface and curing all complete.	Sq.m	307.36			
1.9	Providing and laying granular sub-base on prepared surface, complete as per Drawing and Technical Specifications. [Mechanical Means]	Cu.m	168.08			
1.10	Providing, laying, spreading embankment with borrow material as per Drawing and Technical Specifications.	Cu.m	361.23			
1.11	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. [RCC grade M20]	Cu.m	103.44			
1.12	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. [RCC grade M20] by Ready Mix Concrete (R.M.C)	Cu.m	37.55			
1.13	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications	Kg.	8,650.85			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.14	Providing, Preparing and Installing form work of Class F1 Finish including necessary supports and removing after completion for foundation and footings all complete as per Drawing and Technical Specification. [1804], [1805]	Sq.m	1,016.95			
1.15	Providing and placing 6mm thk.ply for expansion joint with all complete work as per instruction of site incharge.	Sq.m	7.82			

Total Item Price	
VAT (13.00%)	
Grand Total	