Bill of Quantities (BOQ)

Construction of Building : Baraha Kshetra ma vi ,Lungri Ga pa-05, Rolpa

IFB No.: 3500055015/05-SDDO/NCB-083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Information Board	PS	1.00	3,000.00 Three thousand rupees only.	3,000.00 Three thousand rupees only.
PS.2	lab test for materials	PS	1.00	17,000.00 Seventeen thousand rupees only.	17,000.00 Seventeen thousand rupees only.
PS.3	Insurance	PS	1.00	30,000.00 Thirty thousand rupees only.	30,000.00 Thirty thousand rupees only.
	Total provisional sums				50,000.00 Fifty thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Dismalting of stone masonry work with cement mortar	cum	6.76			
1.2	Plain cement Concrete (PCC) for RCC works (1:1.5:3) for column with approved quality of cement and sand and crushed stone aggregate including mixing, laying, curing etc all complete in approval of site engineer.	cum	1.93			
1.3	Formwork, shuttering, centering with approved materials for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support if fully unyielding nett.	sqm	4.90			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Tor steel reinforcement bar of fe 415/500 grade including straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire as per drawing, design & instruction all complete.	kg	135.49			
1.5	Good quality local chimney made Brickwork in 1:4 C/S mortar up to ground floor in perfect line level finishe including wetting the bricks, racking the joints and curing the work for at least 7 days all complete.	cum	24.53			
1.6	Supply and fitting of door and window frame of localwood with including all fitting item as per specification of Site enginner	cum	0.92			
1.7	Supply and fitting of door and window shutter of localwood with including all fitting item as per specification of Site enginner	sqm	31.14			
1.8	12.5mm thick cement plaster in (1:4) ratio on wall of good finish including racking the joint,wetting of surface & curing the work all complete.	sqm	701.16			
1.9	Providing ,supplying and laying 3mm thick cement morter at floor finishing including all complete as per specification	sqm	150.54			
1.10	Providing and laying two coat emulsion painting with one coat primer with proper finishing work all complete as per specification and approval of site Engineer.	sqm	550.62			
1.11	M.S Black & Square pipes for roof trusses with IS or BS section Including Jointing ,Fixing,erection and primer paniting with all necessary MS bed plates ,shoe angles anchor bolts leads sheeting or cement gronting as per drawing and Instruction and all complete	kg	1,355.83			
1.12	26 Guage colour CGI sheet 41mm heavy coated with Hook washer ,Nuts and complete installation works	sqm	298.90			
1.13	24 Guage colour CGI sheet 5mm with Hook washer ,Nuts and complete installation works	sqm	7.85			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.14	Buying and supplying designed gypsum board with frame	sqm	128.02			
1.15	Electric points including switch,charge point,2bulb,indicator, power point,fan etc will all necessary point as per detail work as per specification and approval of Enigeer	point	6.00			

Total Item Price	
VAT (13.00%)	
Grand Total	