Bill of Quantities (BOQ)

Saitol Settlement Development Program, Ribdikot-5, Masar Village Settlement Development Program, Ribdikot -2 and Palung Settlement Development Program, Ribdikot-7, Palpa

IFB No.: 3470150015/UDBOP-NCB-083/84-16

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance premium for the work, plant and materials damage for contract work for the insurance of owner and consultant staff (named); Insurance Premium for construction equipments and machines; Insurance Premium for third party liability personal only	PS	1.00	24,900.00 Twenty-four thousand nine hundred rupees only.	24,900.00 Twenty-four thousand nine hundred rupees only.
PS.2	Material Tests	PS	1.00	22,374.00 Twenty-two thousand three hundred seventy-four rupees only.	22,374.00 Twenty-two thousand three hundred seventy-four rupees only.
PS.3	Supply and Place standard size sign board for Construction Information	PS	1.00	3,000.00 Three thousand rupees only.	3,000.00 Three thousand rupees only.
	Total provisional sums				50,274.00 Fifty thousand two hundred seventy-four rupees only.

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (mechanical means)	cum.	102.83			
1.2	Providing and laying of hand pack Stone soling with stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum.	102.83			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying Reinforcement Cement Concrete RCC(GradeM20)Including batching , mixing, transporting,placing, vibrating ,compactiing,finishing,curing and formwork wherever required,complete in accordance with the approved drawings, DOR Standard Specifications and instructions of the Engineer	cum.	102.83			
1.4	Supplying,cutting,bending and fixing high yield deformed reinforcement steel including binding wire chairs spacers laps and all incidental works complete in accordance with the approved drawing DOR Standard Specifications and instructions of the Engineer	cum.	3,465.65			

Total Item Price	
VAT (13.00%)	
Grand Total	