Bill of Quantities (BOQ)

Upgrading of the Road from Tata Motorable Bridge to Municipal Hospital, Connecting Ward Nos. 10 and 11, Chaurjahaari Municipality Rukum West.

IFB No.: CJM/WORKS/NCB/03/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Providing and Installation of Project SignBoards having details of contract in the format and wording as directed by the site engineer	Ps	1.00	3,500.00 Three thousand five hundred rupees only.	3,500.00 Three thousand five hundred rupees only.
PS.2	Carry out lab tests for material and works as required and instructed by the site Engineer.	Ps	1.00	15,000.00 Fifteen thousand rupees only.	15,000.00 Fifteen thousand rupees only.
PS.3	Insurance of Works,Equipment,Contractor's workmen and employees and third party Insurance against damage to other persons and property.	Ps	1.00	22,500.00 Twenty-two thousand five hundred rupees only.	22,500.00 Twenty-two thousand five hundred rupees only.
	Total provisional sums				41,000.00 Forty-one thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (DOR Norms 905)	cum	149.90			
1.2	Providing and laying of dry stone soling for foundaiton of various structure all complete workas per drawing and Technical Specifications.	cum	139.60			
1.3	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. (Using DOR Norms 2000).PCC Grade M15	cum	19.77			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications. (DOR Norms 2421) Unit = cum (For 10 cum). 60% M 15 concrete and 40% boulders/stones using Mechanical Aids.	cum	100.48			
1.5	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. (Using DOR Norms 2000) PCC Grade M20	cum	133.59			
1.6	Providing , Preparing and Installing form work including necessary supports and removing after completion for walls.(Class F2 Finish), vertical plain surface using timber (soft wood) (DOR Norms 1804,1805 A)	sqm	69.84			
1.7	Providing and Laying Reinforced cement concrete NP3 600 mm internal dia Flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications. (DOR Norms 701)	RM	10.00			
1.8	Providing and laying , fitting and placing un-coated Mild steel / HYSD reinforcement complete in foundation as per drawing and technical specification. (Using DOR Norms 2014)	kg	4,714.83			

Total Item Price	
VAT (13.00%)	
Grand Total	