Bill of Quantities (BOQ)

Bhautik Purbhaadhar (construction Of Building) :Hemantha Aa Vi, Runtigadhi ga pa-03 Rolpa

IFB No.: 3500055015/04-SDDO/NCB-083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Information Board	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
PS.2	lab test for materials	PS	1.00	16,723.80 Sixteen thousand seven hundred twenty-three rupees and eighty paisa only.	16,723.80 Sixteen thousand seven hundred twenty-three rupees and eighty paisa only.
PS.3	Insurance	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
	Total provisional sums				43,723.80 Forty-three thousand seven hundred twenty-three rupees and eighty paisa only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Dismalting of concrete (RCC) column work	cum	0.43			
1.2	Plain cement Concrete (PCC) for RCC works (1:1.5:3) for column with approved quality of cement and sand and crushed stone aggregate including mixing, laying, curing etc all complete in approval of site engineer.	cum	50.32			
1.3	Formwork, shuttering, centering with approved materials for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support if fully unyielding nett.	sqm	420.66			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Tor steel reinforcement bar of fe 415/500 grade including straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire as per drawing, design & instruction all complete.	kg	5,948.70			
1.5	Electrical warring pipe at the slab of building with including the necessary point for fan as per instruction and specification of site Engineer	l/s	1.00			

Total Item Price	
VAT (13.00%)	
Grand Total	