Bill of Quantities (BOQ)

Kopawa Prahari Chauki dekhi Dakshin Daharchandi samma Nali Nirman, Banganga Na. Pa. 5

IFB No.: 3370149015/02/RIDOKAP/10134/SQ/083-84/20

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Supply, place and maintain standard size 0.9 x 1.2 m sign board for Project information and Prepare and submit progress report/Final Report with Color prints in A4 size paper color photo and video.[110]	No.	1.00			
1.2	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including scaffolding wherever necessary, sorting the dismantled Material, disposal of unserviceable Material and stacking the serviceable Material with all lifts and lead of 1000 meters, Dismantling Stone Masonry/ Brick Masonry	Cum	13.00			
1.3	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cium	106.25			
1.4	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per Drawing and Technical Specifications. (Mechanical Means)	Cium	36.00			
1.5	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cium	34.57			
1.6	Providing and laying of PCC (Grade M 10) in foundation complete as per Drawing and Technical Specifications	Cium	28.81			
1.7	Providing and laying of RCC (Grade M 20) in foundation complete as per Drawing and Technical Specifications	Cium	70.05			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.8	Providing and laying, fitting and placing HYSD bar reinforcement in super-structure complete as per Drawing and Technical Specifications	Ton	3.76			
1.9	Supply & place naturally found or quarry sieved loose gravel material including levelling all completes as per Specifications.[1201]	Cum	5.00			

Total Item Price	
VAT (13.00%)	
Grand Total	