Bill of Quantities (BOQ)

Baghshala Ghamailo Kakani View Tower Road Upgrading, Kakani Rural Municipality, Nuwakot

IFB No.: IDONUWAKOT/W/NCB/6/2083-84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property(GCC 13)	PS	1.00	40,000.00 Forty thousand rupees only.	40,000.00 Forty thousand rupees only.
PS.2	Carry out additional tests for material and works as required and instructed by the Project Manager.(GCC 33.1)	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.3	Provide and maintain traffic safety, Occupation Health and Safety (OHS) as per special provision,control measures and temporary diversions during construction as instructed by the Engineer.(DoR SS 104)	PS	1.00	15,000.00 Fifteen thousand rupees only.	15,000.00 Fifteen thousand rupees only.
	Total provisional sums				65,000.00 Sixty-five thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Provide and installation of project information board of size 1.80 m X 1.2 m along with iron posts including excavation, concreting,backfilling etc all complete as per DoR Standard Specification for Road and Bridge Works.(DoR SS 110)	No	1.00			
1.2	Earthwork in excavation of Foundation of structures for all types of soil , including construction of shorring and bracing, removal of stumps and other deleterious matter and backfilling with aproved materials as per drawing and technical specification.(DoR SS 907)	Cum	224.30			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.(DoR SS 1006)	Cum	168.23			
1.4	Providing and laying of Plain/Reinforced Cement Concrete M20 (1:1.5:3) Including FormWorks in Foundation complete as per Drawing and Technical Specifications.(DoR SS 2000)	Cum	224.30			
1.5	Providing and laying , fitting and placing un-coated Mild steel / HYSD reinforcement complete in foundation as per drawing and technical specification(DoR SS 2014)	MT	7.06			

Total Item Price	
VAT (13.00%)	
Grand Total	