Bill of Quantities (BOQ)

Construction of P.C.C. Road in Mathillo Khaireni Rajesh Mallah to Batuli GHar,ward 2 & Belwa Ma.Bi. to North Bhagalapur Village Road ward 1

IFB No.: 50806/NCB/SRM/10/083-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Provision for Lab test according to standard specfication,Unforessen works & Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.	PS	1.00	75,000.00 Seventy-five thousand rupees only.	75,000.00 Seventy-five thousand rupees only.
	Total provisional sums				75,000.00 Seventy-five thousand rupees only.

Concrete work CPV: 45262300-4 - Concrete work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Supply and Installation of Project Information Board of size 1.2 m by 1.5m,diversion boards,Job Boards as per the Instruction of Engineer .	No	2.00			
1.2	Scarifying the exisiting granular road surface to depth of 50mm and Disposal of Scarified Material with in all lifts and leads As per Drawiing and Technical Specifications.Lead up to 30m.	M2	2,610.00			
1.3	Providing and Laying granular Sub-Base on prepared surface ,Mixing at OMC,And Compacting to achive the desired density ,Complete as per Drawing and Technical Specifications.By Mechanical Means	M3	365.40			
1.4	Providing and Laying of Plain Cement Concrete in Foundation Complete as per Drawing and Technical Specifications.PCC Grade M15(Including with plywood for Expansion joint As per Requied)	M3	292.50			
1.5	Providing ,Preparing and Installing Form work Including Necessary supports and removing after completion for foundation and footings.(Class F1 finish)Using Steel.	M2	72.50			

Concrete work CPV: 45262300-4 - Concrete work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.6	Construction of Embankment Both side of Shoulder with Material obtained from Borrow pits Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications.	M3	52.20			
1.7	Providing of 4MM THICKNESS Plywood of sufficient Height for expansion Joints as per Technical specification & instruction of site engineer.	M2	90.62			

Total Item Price	
VAT (13.00%)	
Grand Total	