Bill of Quantities (BOQ)

Upgrading Works of Panchami Bazar Road Pyang

IFB No.: 801010307/MJRM/NCB/WORKS /083/084-08

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the damage and loss of works,plants,and vehicles;personal injuries,death of labours,Employees and other third party Insurance	PS	1.00	17,000.00 Seventeen thousand rupees only.	17,000.00 Seventeen thousand rupees only.
PS.2	Construction materials test as directed by site Engineer	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.3	1500 x 1200 mm Size Site information board as specified	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				29,000.00 Twenty-nine thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (MECHANICAL MEANS)	cum	111.90			
1.2	Stone pitching/ Soling work on the prepared bedding with filling of voids by granular material/ spalls as per direction of the engineer all complete	cum	68.55			
1.3	"Providing, Preparing and Installing form work including necessary supports and removing after completion for precast element/ all type of structures. Class F3 Finish I) Square/ Rectangular/ Circular Sections/ Verticle surfaces a) Using Timber & Plywood"	sqm	84.50			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying of Plain/ Reinforced Cement Concrete (RCC Grade M20) in Foundation complete as per Drawing and Technical Specifications.	cum	77.65			

Total Item Price	
VAT (13.00%)	
Grand Total	