Bill of Quantities (BOQ)

Upgrading Of Ramshahghat Raikarbesi Aarubot Manakamna Road Sahidlakhan R.M-02, Gorkha

IFB No.: 3370136014/IDO/GORKHA/NCB/W/R/20/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.[GCC19]	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
	Total provisional sums				25,000.00 Twenty-five thousand rupees only.

Construction work-Road Construction Work **CPV: 45000000-7 - Construction work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing and installation of project signboards as per specification and instruction of engineer.	Nos	1.00			
1.2	Earth work in excavation of foundation of structures in all types of soil including Rock, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. [SSRBW-907]	Cum	306.53			
1.3	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications[SSRBW 2602,2603,2607].	Cum	68.47			
1.4	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications[SSRBW 1006].	Cum	56.94			
1.5	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork) [SSRBW: 2000]	Cum	16.08			

Construction work-Road Construction Work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.6	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M20 (Including Formwork) [SSRBW: 2000]	Cum	43.08			
1.7	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications [SSRBW: 2014]	KG	1,762.62			
1.8	Supply of machine made hexagonal mesh type 100mm x 120 mm Gabion boxes / mattresses with diapharagms, with binding wire x swg, mesh wire 3mm and selvedged wire 3.9 mm and lacing wire 2.4 mm, including palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, beding, bonding and all transporation as per specification. [SSRBW: 2401,2402]	Cum	48.00			
1.9	Providing, laying and fixing of Geo-textile (filter fabrics), lead 30m[SSRBW: 2404]	Sqm	27.00			

Total Item Price	
VAT (13.00%)	
Grand Total	