Bill of Quantities (BOQ)

Chauthi bazar purbadhar nirman

IFB No.: KUMMAYAKRM/2083-084/KRM-NCB-03

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, Plants, materials,loss and damage to equipments, Contractor's workmen,employees and third party insurance against damage to other persond and property.	PS	1.00	65,000.00 Sixty-five thousand rupees only.	65,000.00 Sixty-five thousand rupees only.
PS.2	Carry out additional tests for material and works as required and instructed by engineer.	PS	1.00	1,00,000.00 One lakh rupees only.	1,00,000.00 One lakh rupees only.
PS.3	Provide and installation of project information board size 1.8 X 1.2 m along with iron posts including excavation ,concreting, backfilling all complete as per Specification.	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
	Total provisional sums				1,70,000.00 One lakh seventy thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork in excavtion including levelling of undulation ground, removing of soil.	Cum	756.00			
1.2	Transportation of soil by truck 500 mtr including truck, safely dumping.	Cum	756.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying in position machine mixed and machine vibrated cement concrete of mix 1:1.5:3 (1 cement:1.5 sand: 3 coarse	Cum	214.28			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
	aggreagate) M20 grade for reinforced cement concrete work using approved cement with 20 mm graded crushed stone aggregate of approved quality in various locations and heights including transportation of concrete to site of placing, compaction, finished to required line and level, protection and curing, etc. all complete as per drawings, specifications and the instructions of the Engineer.					
1.4	Stone Soling Work in Foundation including haulage upto 30 meter distance	Cum	190.16			
1.5	Cement Concrete Work in Foundation, Wall etc. including haulage upto 30 meter distance. (Aggregate From Crusher) 1:3:6	Cum	8.01			
1.6	Stone Masonry Work upto 5 meter mason height and haulage upto 10 meter distance. (Stone Feom Quarry) 1:6	Cum	1.61			
1.7	Providing and laying Reinforcement including cutting, bending, binding, fixing in position and lead 30m. etc. all complete as per specification and drawing.	kg	9,689.84			
1.8	Form Work including providing material, fixing and removing .	Sqm	126.00			

Total Item Price	
VAT (13.00%)	
Grand Total	