Bill of Quantities (BOQ)

Dalit Samudayka Lagi Suddha Khanepani Ek Ghar Ek Dhara Karykaram.

IFB No.: 80774402300/80774402300/PTNMUN/WORKS/2083/084-04

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Cost for complying with any other requirement (study or construction) not covered in BOQ, General or particular conditions of contract which may have a financial implication and necessary to complete the work during the construction and operation period as instructed and approved by the engineer.	PS	1.00	30,000.00 Thirty thousand rupees only.	30,000.00 Thirty thousand rupees only.
	Total provisional sums				30,000.00 Thirty thousand rupees only.

Civil Work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork excavation in soft soil mixed with clay & silty including removing up to 10 mtr. Lead & lift up to 1.5 mtr. Engineer.	cum	450.25			
1.2	Dry stone soling in foundation /boulder packing.	cum	5.22			
1.3	P.C.C. work in 1:3:6 in foundation wall & carrying lead up to 30 mtr.	cum	2.05			
1.4	P.C.C(1:1.5:3) work for super structure with 2% Water Proofing Chemical (W.P.C)	cum	20.54			
1.5	Steel reinforcement work.	kg	1,612.39			
1.6	19 mm thick waterproof Forwork.	sqm	201.54			
1.7	1:4 Stone Masonry Work For Intake.	cum	5.68			
1.8	12.5 mm thick 1:3 c-s plaster with 2% W.P.C.	sqm	224.46			

Civil Work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.9	3 mm thick Punning Work.	sqm	108.66			

Procurement, Supplying and Fitting Items for RVT Tank and Intake Chamber						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.1	25mm GI Outlet Pipe	rm	5.20			
2.2	32mm GI Inlet Pipe	rm	4.39			
2.3	32mm GI Outlet Pipe	rm	6.60			
2.4	20mm GI Overflow Pipe	rm	3.99			
2.5	32mm GI Washout Pipe	rm	4.00			
2.6	Gate Valve (size below 50 mm)	nos	23.00			
2.7	Procurement and Supplying of 20mm HDPE (NS 40).PE 100, PN 16.00 kg/cm2	rm	1,085.00			
2.8	Procurement and Supplying of 25 mm HDPE (NS 40). PE 100, PN 16.00 kg/cm2	rm	2,800.00			
2.9	Procurement and Supplying of 32mm HDPE (NS 40). PE 100, PN 16.00 kg/cm2 .	rm	600.00			

Total Item Price	
VAT (13.00%)	
Grand Total	