Bill of Quantities (BOQ)

Construction of Building of ShreePadma Kumari Ma.Vi. Rajapur-05 Jaipur, Bardiya

IFB No.: 3500057025/SDDOBANKE/W/NCB-03/2083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Supplying and erecting 1.5m.x 1.2m. size Project Sign Board in place including 50mm dia. Steel tube, 2mm. thick steel plate, cement concrete, painting, writing and supporting steel angle nut and bolit etc. all complete	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
PS.2	Carrying out diferrent laboratory tests of construction material like cement, rod, bricks, sand, aggregate, filling materials, concrete cubes etc. during construction work as per specification and direction.	PS	1.00	11,500.00 Eleven thousand five hundred rupees only.	11,500.00 Eleven thousand five hundred rupees only.
PS.3	Insurance premium for the work, plant and materials damage for the contract work for all risk including riot, strike, damage, malicious damage and terrorism for contract work of accepted amount for 15 months +1 year maintainance period.	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
	Total provisional sums				41,500.00 Forty-one thousand five hundred rupees only.

Education and training services CPV: 80000000-4 - Education and training services						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork in excavation in medium type soils in foundation including 10m hauling distance and 1.5 m. lift all complete in approval of site engineer.	Cum	80.81			
1.2	Earth filling of Excavated surface in 150 mm thick layer, watering, ramming including supply of filling materials within 10 m distance all complete as per approved drawing,Specification and instruction of site engineer.	Cum	48.49			

Education and training services
CPV: 80000000-4 - Education and training services

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.3	Filling with approved soil(transported soil from outside) into the flooring of building/structure/ground.Back filling materials shall be appiled on layers by layers of 150mm thick, watering and compaction and all complete as per approved drawing, Specification and instruction of site engineer.	Cum	38.19			
1.4	Supplying and Stone soling in proper line and level with sand filling all complete as per approved drawing, Specification and instruction of site engineer.	Cum	6.17			
1.5	Plain cement Concrete (PCC) in 1:3:6 ratio for foundations and flooring with approved quality of 43 Grade Of Opc cement, Crusher sand and machine crushed 20MM down stone aggregate including supply of materials,Mixture mixing, laying, curing the work at least 7 days etc all complete as per approved drawing, Specification and instruction of site engineer.	Cum	4.63			
1.6	Good quality local chimney made Brickwork in 1:4 C/S mortar in superstructure in perfect line level finish including supply of materials, wetting the bricks, racking the joints and curing the work for at least 7 days all complete as per approved drawing, Specification and instruction of site engineer.	Cu.m.	19.17			
1.7	Plain cement Concrete (PCC) for RCC worksM20(1:1.5:3) for slab/lintels/columns/beams with approved quality of (43 grade) OPC Cement, Crusher sand and machine crushed 20MM down stone aggregate including supply of materials,Mixture mixing, laying, curing the work at least 7 days etc all complete as per approved drawing, Specification and instruction of site engineer.	Cu.m.	54.03			
1.8	TMT steel reinforcement bar of fe 500 grade including supplying, straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire all complete as per approved drawing, Specification and instruction of site engineer.	Kg.	6,856.73			

Education and training services CPV: 80000000-4 - Education and training services						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.9	Formwork, shuttering, centering with 19mm thick waterproof ply board and steel post for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support if fully unyielding nett all complete as per approved drawing, Specification and instruction of site engineer.	Sq.m.	364.98			
1.10	Supplying and fitting of PVC pipe 25mm for wirring System of Fan box, light box etc all complete as per the drawings and instructions of site Engineer	Rm	75.00			

Total Item Price	
VAT (13.00%)	
Grand Total	