Bill of Quantities (BOQ)

Upgrading of Dharmasala Musurabari Prajatanra Pra.Bi. Bhuderumta Chihane Gahira Baraili Kul Mandir To Sundarbasti Road Baglung Municipality-13 Baglung

IFB No.: 3370145034/IDOBAGLUNG/NCB/W/R/60/2083/84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property as per GCC clause 13.	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
PS.2	Relocation for public utilities such as Electric Pole,Irrigation pipe ,water supply,Skilled ,Unskilled Man Power & Other Unseen Works .	PS	1.00	44,000.00 Forty-four thousand rupees only.	44,000.00 Forty-four thousand rupees only.
	Total provisional sums				64,000.00 Sixty-four thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m having details of contract in the format and wording as directed by the Engineer.(SSRBW 110)	Nos	1.00			
1.2	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled Material up to a lead of 1000 metres, stacking serviceable and unserviceable Material separately(SSRBW 202)	Cu.m	1.35			
1.3	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. Ordinary soil Mechanical Means (SSRBW 907)	Cu.m	221.96			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying of hand pack Stone soling and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.(SSRBW1006)	Cum	33.02			
1.5	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork,Curring,Testing)(SSRBW2000)	Cum	30.63			
1.6	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M25 (Including Formwork,Curring,Testing)(SSRBW2000)	Cum	7.80			
1.7	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications.(SSRBW2014)	KG	639.98			
1.8	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Foundation complete as per drawing and technical specification.(Icluding Curring,Testing, HDPE Pipe Weep holes) Machine Mixed Mortar(SSRBW2600,2607)	Cum	84.67			
1.9	Providing and Pointing with cement mortar on masonry work in structure as per Technical Specifications (cement mortar 1:3)(2600,2607)	Sqm	78.50			
1.10	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications 60% M 15 concrete and 40% boulders/stones using Mechanical Aids(SSRBW3113)	Cum	48.96			

Total Item Price	
VAT (13.00%)	
Grand Total	