Bill of Quantities (BOQ)

Combined Package for the Construction of Bakleko Dhara to Thulopakha Road and Rigid Pavement Works of Bakleko Dhara – Harrabot – Thulopakha Krishi Sadak, Modi -5, Parbat

IFB No.: 3370142014/IDOP/NCB/W/11/2083-84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance of works, plants, materials, loss and damage to equipment, contractor's workmen and employees and third party insurance against damage to other persons and property as per specifications and instructions of the engineer (GCC 19)	PS	1.00	1,00,000.00 One lakh rupees only.	1,00,000.00 One lakh rupees only.
PS.2	Relocation of services and minor infrastructures as per specification and instructions of the engineer (SSRBW 105)	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
	Total provisional sums				1,50,000.00 One lakh fifty thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Earthwork in excavation of foundation of structures in all types of soil an rock by mechanical means, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 900, 907)	m^3	22.65			
1.2	Providing and laying of hand packed stone soling with 150 to 200 mm thick stones and packing with smaller stones on prepared surface as per drawings, technical specifications and instructions of the engineer (SSRBW 1000, 3111)	m^3	2.36			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying plum concrete including formworks (60% machine-mixed M15 concrete and 40% boulders / stone) including providing weep holes (not required in drain), all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2400, 2421)	m^3	42.94			
1.4	Compacting original ground supporting sub-grade: Loosening of the ground up toa level of 500 mm below the sub-grade level, watering, grading and compacting in layers as per drawings, technical specifications and instructions of the engineer	m^3	1,333.09			
1.5	Providing and laying of 90 GSM plastic sheet over prepared surface, as per drawings, technical specifications, and as directed by the Engineer.	m^2	2,666.18			
1.6	Providing and laying of M20 concrete for RCC including formworks, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2000)	m^3	533.24			
1.7	Providing and laying, fitting and placing HYSD reinforcement, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2000, 2014)	kg	2,562.25			

Total Item Price	
VAT (13.00%)	
Grand Total	