Bill of Quantities (BOQ)

Shree Shahid Basu Smriti Aa Bi ma Field Nirman

IFB No.: 3500056025/NCB/WORKS/SDDOD/02/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance premium for the work, plant and materials damage for contract work for all risk including Riot, Strike, Damage, Malicious damage for contract work	P.S	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.2	Carry out additional test for Heavy coated G.I wire as required and instructed by the Engineer	P.S	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.3	Supply and install Project project sign board of size 0.9m X 1.2 m including painting, writing complete as per the instruction of Engineer	P.S	1.00	2,500.00 Two thousand five hundred rupees only.	2,500.00 Two thousand five hundred rupees only.
	Total provisional sums				37,500.00 Thirty-seven thousand five hundred rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Site clearance before and after all complete as per design, drawing, specification and instruction of site incharge.	L/s	1.00			
1.4	Providing suitable material and Back filling behind Gabbion,abutment, wing wall and return wall complete as per Drawing and Technical Specifications.	cu.m	4,468.80			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Supply of Machine Made Gabion boxes / mattresses with diapharagms including rolling, cutting and weaving as per specification. Including Providing and filling stone / boulder in gabion boxes / mattress etc. including dressing, beding, bonding and all transportation as per Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -3mm (0.0615 kg/m) & selvedge wire -3.9mm(0.1057kg/m) and Binding wire 12 SWG Box of different sizes as per requirements. (different size 1 m height Gabion box)	cu.m	184.00			
1.6	Supply and laying of geo textile filter under gabion boulder filling all complete as directed by the Engineer.	m2	108.00			

Total Item Price	
VAT (13.00%)	
Grand Total	