Bill of Quantities (BOQ)

Upgrading of Rakse Manglabare Road,Deumai Municipality,Ilam

IFB No.: 3370103011/IDOILAM/NCB/W/08/83/84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for loss or damage to works, plant, material, equipment, property and personnel injury or death and third party as per contract data and technical specifiation (Cl. 19 of CoC)	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
PS.2	Carrying out laboratory and field tests on materials and completed works, as required and as directed by the Engineer, including all necessary arrangements and incidental works, complete.	PS	1.00	1,000.00 One thousand rupees only.	1,000.00 One thousand rupees only.
PS.3	Providing, writing and installation of the project information board as per the Standard Specifications and approved drawings and as instructed by the Engineer.	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				23,000.00 Twenty-three thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. [Spec. cl. No: 907]	Cum	199.00			
1.2	Providing,laying and levelling of hand packed Stone soling with 100 mm to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications and Engineer's Instruction.	Cum	348.50			

Total Item Price	
VAT (13.00%)	
Grand Total	