Bill of Quantities (BOQ)

Construction Of Tallo Ijarmode-Chaule Gaira-Mulemare-Kulsibang-Dhaireni-Lamakhet Road

IFB No.: 80659501300/TRM/TCMKDL/NCB/R/01/2083/084 (RE)

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss or damage to works, pant, material, equiment, property, contractor's emloyees and labour, employer's and consultants's staff personnal injury or death and third party property and persons during the construction period and upto the end of defects liability period as per the condition of contract	ps	1.00	2,00,000.00 Two lakh rupees only.	2,00,000.00 Two lakh rupees only.
PS.2	Provision of laboratory tests as required (Cement, Reinforcemnt, Sand , Brick, Aggregate etc) and other lab tests like seive, utm, cube mould, slump testing as per the specification and instructions of the Site engineers.	ps	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
PS.3	Provide and installation of project information board including excavation, concreting , back filling etc. all complete as per DoR standard specification for road and bridge	ps	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				2,60,000.00 Two lakh sixty thousand rupees only.

Works for complete or part construction and civil engineering work **CPV: 45200000-9 - Works for complete or part construction and civil engineering work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork Excavation in cutting., Roadway excavation in ALL TYPE OF SOIL,ORDINARY ROCK AND HARD ROCK by Mechanical means, as per drawing and technical specifications including disposalat safe site up removal all lift and lead as per of stumps and other deteterious matter, all lifts drawing and instruction of the site engineer.	cum	51,624.50			
1.2	Removal of unserviceable soil and rock including loading and disposal upto 100 meters lead and instruction of the site engineer.	cum	2,008.50			

Works for complete or part construction and civil engineering work
CPV: 45200000-9 - Works for complete or part construction and civil engineering work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.3	Earthwork Excavation in Foundation excavation in ALL TYPE OF SOIL AND ROCK by Mechanical means, as per drawing and technical specifications including removal of stumps and other deteterious matter, all lifts and lead as per drawing and instruction of the site engineer.	cum	350.95			
1.4	Providing and plain cement concrete M15(1:2:4) including placing compacting and testing etc all complete as per specification and instruction of the site engineer.	cum	44.35			
1.5	Providing and laying of dry stone solling for foundation works of all complete as per specificationand instruction of the site engineer.	cum	46.90			
1.6	Providing and laying random rubble stone masonary in cement sand morter (1:4) including scaffolding , curing prepration of morter etc all complete as per specification and instruction of the site engineer.	cum	204.75			
1.7	Supply and febrication assembling and fixing in position of Machine made heavy coated Gabion boxes / matresses of heagonal mesh type 100mm*120mm with mesh wire 10 swg , selvage wire 8swg binding wire 12swg and supply transport as per specification (Size 1.5*1*1, 2*1*1 and 3*1*1)	sqm	6,887.00			
1.8	Gabion boxes stone filling works all complete as per instruction of the site engineer.	cum	1,278.00			
1.9	Supplying, cutting, bending and placing in position as per drawings and specification and binding by binding wire of reinforcement steel bars for R.C.C works including haulage upto 30m. Manual Means	kg	971.46			
1.10	Form work with Local Soft wood	sqm	21.60			

Total Item Price	
VAT (13.00%)	
Grand Total	