Bill of Quantities (BOQ)

Construction of Remaining Building of Suryodaya Aadharbhut Bidhyalaya

IFB No.: 801054801/08/BSMC/IDD/WORKS/NCB-083-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Supply and placing project information board/ hoarding boards, carryout necessary lab test and photography of work, event and materials as per requirement and instruction, all complete	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.2	Insurance for the loss or damage to works, plants, materials, equipment, property and personal injury or death including Employer, Contractor and third parties as per conditions of contract.	PS	1.00	30,000.00 Thirty thousand rupees only.	30,000.00 Thirty thousand rupees only.
PS.3	Provisional Sum for electrical & sanitary work as per instructed by an engineer.	PS	1.00	1,45,000.00 One lakh forty-five thousand rupees only.	1,45,000.00 One lakh forty-five thousand rupees only.
PS.4	Provisional Sum for any relevant unforeseen work items as necessitated and instructed by an engineer.	PS	1.00	19,500.00 Nineteen thousand five hundred rupees only.	19,500.00 Nineteen thousand five hundred rupees only.
	Total provisional sums				2,04,500.00 Two lakh four thousand five hundred rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork in excavation in foundation of structures all complete	Cum	19.56			
1.2	Providing suitable material and Back filling with Locally available Material including compaction all complete	CUm	2.40			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Stone soling in sand in foundations and bedding of structures including providing of materials and all complete	Cum	31.45			
1.4	Providing and laying Machine Mixed Plain Cement Concrete M15 (PCC 1:2:4) including compaction in required lines and level with necessary scafolding, curing and all complete	Cum	25.872			
1.5	Providing and laying M20 grade Machine Mixed Concrete (PCC 1:1.5:3) for RCC of Culvert Bed, Abutments, Deck Slabs of Culverts and Drain Covers, Parking Lots, etc. including compaction in required shapes, lines and level with necessary scafolding, curing and all complete	Cum	97.159			
1.6	Supplying, cutting, bending, binding and placing in position of TMT Bars for reinforcement steel, all complete	Kg	10,614.82			
1.7	Providing and laying 1st Class Brick Masonry work in cement sand (1:4) mortar including necessary scaffolding, lining, levelling, curing and all complete	Cum	62.17			
1.8	Providing, preparing and installing formwork including necessary supports and removing after completion for all works complete	Sqm	698.25			
1.9	Providing and applying 12.5 mm thick Plaster with cement mortar on brick work structure as per Technical Specifications Cement Mortar 1:4 (1 cement : 4 sand)	Sqm	766.54			

Total Item Price	
VAT (13.00%)	
Grand Total	