Bill of Quantities (BOQ)

Sukhawodar Jayachaur Tapla Ratamata Motorbato Starunnati tatha Nirman

IFB No.: 50204/GRM/NCB/WORKS/083/084-01

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Information Display Board	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
PS.2	Material Lab Test	PS	1.00	15,000.00 Fifteen thousand rupees only.	15,000.00 Fifteen thousand rupees only.
PS.3	Insurance of works, equipments,contractor's workmen and third party Insurance against damage to other persons and property.	PS	1.00	35,000.00 Thirty-five thousand rupees only.	35,000.00 Thirty-five thousand rupees only.
	Total provisional sums				55,000.00 Fifty-five thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Road way Excavation in all types of soil and all types of rocks by Mechanical Means as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer.	cum	23,165.25			
1.2	Supplying and Stone soling in proper line and level with sand filling all complete as per approved drawing, Specification and instruction of site engineer.	cum	70.85			
1.3	Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.	cum	53.14			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying of Plain/Reinforced Cement Concrete for Rigid Pavement complete as per Drawing and Technical Specifications., RCC Grade M30 including formwork	cum	84.00			
1.5	Supplying and Fixing of steel reinforcement bar including Bending ,binding TMT reinforcement bar with and placing in position as per drawing specification and instruction all complete.	kg	2,002.50			
1.6	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications, 60% M 15 concrete and 40% boulders/stones, using Mechanical Aids	cum	67.20			
1.7	Formwork, shuttering, centering with 19mm thick waterproof ply board and steel post for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support if fully unyielding nett all complete as per approved drawing, Specification and instruction of site engineer.	sqm	128.70			
1.8	Rubble masonry in 1:6 C/S mortar in perfect line level finish including, racking the joints and curing the work for at least 7 days all complete.	cum	70.00			
1.9	Providing and laying mechanical woven Gabion boxes /mattresses, placing in position including stretching; forming compartments; tying the sides and diaphragms with binding wire in each mesh; tying with bracing wires and tie wires, tying down the lid and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications. (Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selvage wire 3.9 mm, lacing wire 2.4 mm)	cum	190.00			

Total Item Price	
VAT (13.00%)	
Grand Total	