Bill of Quantities (BOQ)

Upgrading of Balimtar Hudaie Dhawa Jane Sadak And Narayan than Dekhi Dhawa Sadak Bhimsenthapa -04,Gorkha

IFB No.: 3370136014/IDO/GORKHA/NCB/W/R/38/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.[SS DOR GCC19]	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
PS.2	Relocation of Services and repairing for existing infrastructure (houses, water supply pipes, HDPE pipes, Electric Poles, Temple, Foot staircase, Foot trail etc) for social and environmental compliance as instructed by engineer's. [SSRBW Clause 105]	PS	1.00	30,000.00 Thirty thousand rupees only.	30,000.00 Thirty thousand rupees only.
	Total provisional sums				80,000.00 Eighty thousand rupees only.

Balimtar Hudaie Dhawa Jane Sadak **CPV: 45000000-7 - Construction work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer[SS DOR 110]	Nos	1.00			
1.2	Road way Excavation in all types of soil, Ordinary Rock & hard Rock(using Breaker) as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. SSRBW 905.	Cum	432.36			
1.3	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications[SS DOR 2602,2603,2607].	Cum	42.00			
1.4	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications[SS DOR 1006].	Cum	75.75			

Balimtar Hudaie Dhawa Jane Sadak
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.5	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork)SSRBW: 2000	Cum	25.78			
1.6	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M20 (Including Formwork)SSRBW: 2000	Cum	59.40			
1.7	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications SSRBW: 2014	KG	2,501.54			

Narayan than Dekhi Dhawa Sadak Bhimsenthapa -04,Gorkha
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.8	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer[SS DOR 110]	Nos	1.00			
1.9	Road way Excavation in all types of soil, Ordinary Rock & hard Rock(using Breaker) as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. SSRBW 905.	Cum	302.10			
1.10	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications[SS DOR 2602,2603,2607].	Cum	86.00			
1.11	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications[SS DOR 1006].	Cum	65.85			

Narayan than Dekhi Dhawa Sadak Bhimsenthapa -04,Gorkha CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.12	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork)SSRBW: 2000	Cum	7.38			
1.13	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M20 (Including Formwork)SSRBW: 2000	Cum	52.50			
1.14	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications SSRBW: 2014	KG	2,206.79			

Total Item Price	
VAT (13.00%)	
Grand Total	