Bill of Quantities (BOQ)

Upgrading of Kakrebihar Tole Bata Dakshin Tarfa Jyoti BK Ko Ghar Hudai Eklai Rukh Janey Sadak, Bi. Na. Pa-10, Surkhet

IFB No.: 3370168016/02-IDO/SKT/W/NCB/11/083-084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss or damage to works, plant, material, equipment, property, Contractor's employees and labour, Employer's and Consultants's staff personnel injury or death and third party property and persons during the construction period and upto the end of defects liability period as per the condition of contract.	PS	1.00	45,000.00 Forty-five thousand rupees only.	45,000.00 Forty-five thousand rupees only.
PS.2	Carry out additional tests for material and works as required and instructed by the Project Manager.	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
	Total provisional sums				70,000.00 Seventy thousand rupees only.

General Item						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Provide and installation of project information board of size 1.80 m X 1.2 m along with iron posts including excavation, concreting,backfillingetc all complete as per DoR Standard Specifixcation for Road and Bridge Works.	Nos	1.00			

Drain Construction Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.1	Earthwork Excavation in all types of soil including hard rock of foundation and trenches including construction of shoring and bracing, removal of stumps and other deleterious matter as per drawing and technical specifications.	Cum	267.75			

Drain Construction Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum	97.02			
2.3	Providing and laying of Plain/Reinforced Cement Concrete in structures complete including formwork as per Drawing and Technical Specifications, PCC Grade M 15.	Cum	218.68			
2.4	Providing and laying of Plain/Reinforced Cement Concrete in structures complete including formwork as per Drawing and Technical Specifications, PCC Grade M 20.	Cum	5.00			
2.5	Providing and laying , fitting and placing Mild steel / HYSD reinforcement complete in sub-structure/super-strucure as per drawing and technical specification.	MT	0.48			

Pavement Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
3.1	Compacting original ground supporting sub-grade Loosening of the ground upto a level of 500 mm below the sub-grade level, watered, graded and compacted in layers as per Drawing and Technical Specifications	Cum	558.00			
3.2	Providing and laying natural granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications., By Mechanical means.	Cum	279.00			

Total Item Price	
VAT (13.00%)	
Grand Total	