Bill of Quantities (BOQ)

construction work of nayatar sinchai yojana

IFB No.: 438/05/NCB/WORKS/GRM/2083-084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Provisional Sum	PS	1.00	94,000.00 Ninety-four thousand rupees only.	94,000.00 Ninety-four thousand rupees only.
	Total provisional sums				94,000.00 Ninety-four thousand rupees only.

Construction materials CPV: 44110000-4 - Construction materials						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	excavtion in hard soil by mechanical means	CU.M	1,488.00			
1.2	excavtion in medium rock by mechanical means(breaker/exavetar) including removal of stumps and other deleterious matter, with all lifts and lead	CU.M	66.00			
1.3	Stone soling	CU.M	59.10			
1.4	providing and laying plain cement concrete(M15 PCC grade) as per drawing by manual work with formwork	CU.M	1.60			
1.5	Dewatering work for this whole work	DAY	10.00			
1.6	providing and laying plain/reinforcement cement concrete(M25 PCC grade) as per drawing by mechanical means	CU.M	99.57			
1.7	providing and laying plain/reinforcement cement concrete(M20 PCC grade) as per drawing by mechanical means work with formwork	CU.M	106.80			

Construction materials CPV: 44110000-4 - Construction materials						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.8	Activity : Providing and laying Plum concrete (Boulder mixed concrete-60%M15 concrete and 40% boulders/stones) as per Drawing and Specifications by manual means including formworks.	CU.M	255.30			
1.9	stone masonary work at 1:6	CU.M	26.325			
1.10	Reinforcement	KG	11,937.669002			
1.11	formwork	SQ.M	117.60			
1.12	Activity : Making and filling gabion incl. cutting wire, netting ,stone filling etc complete Mesh wire-10 Swg (0.0615 kg/m), Selvedge wire 8 Swg (0.1057 kg/m), binding wire 12 Swg (0.049 kg/m) Hexagonal mesh type 100 mm X 120 mm, Box size 2x1x1 m (11 sqm)	NUM	1.00			
1.13	new metal gate with steering (metal sheet, metal frame and others)for water control with needed structure as per site and next one metal gate repair and fit as per needed	LS	2.00			

Total Item Price	
VAT (13.00%)	
Grand Total	