Bill of Quantities (BOQ)

Upgrading Of Khabdi Bhanjyang Healthpost To Sahid Smriti Bhawan Road Sahidlakhan RM-07, Gorkha

IFB No.: 3370136014/IDO/GORKHA/NCB/W/R/23/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.[SS DOR GCC19]	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
	Total provisional sums				25,000.00 Twenty-five thousand rupees only.

Road Construction work **CPV: 45000000-7 - Construction work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer[SS DOR 110]	Nos	1.00			
1.2	Earth work in excavation of foundation of structures in all type of soil including rock,including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications.[SS DOR-907]	Cum	241.68			
1.3	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications[SS DOR 2602,2603,2607].	Cum	101.00			
1.4	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications[SS DOR 1006].	Cum	61.89			
1.5	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork)SSRBW: 2000	Cum	8.64			

Road Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.6	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M20 (Including Formwork)SSRBW: 2000	Cum	48.95			
1.7	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications SSRBW: 2014	KG	1,609.38			

Total Item Price	
VAT (13.00%)	
Grand Total	