Bill of Quantities (BOQ)

Upgrading of Patle Khola Gade Khola Road, Ajirkot-03, Gorkha

IFB No.: 3370136014/IDO/GORKHA/NCB/W/R/39/083/084

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.[SS DOR GCC19]	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.2	Reallocation of services and minor infrastructures and Environment Protection Work as per specification and as instructed by the Project Manager.[SP/SS-111]	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
	Total provisional sums				50,000.00 Fifty thousand rupees only.

Road Construction work > General Items
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer[SS DOR 110]	Nos	1.00			

Road Construction work > Earthworkd
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.2	Road way Excavation in all types of soil, Ordinary Rock & hard Rock(using Breaker) as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. SSRBW 905.	Cum	1,142.37			

Road Construction work > Structure & Cross Drainage Works CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications[SS DOR 2602,2603,2607].	Cum	42.00			
1.4	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications[SS DOR 1006].	Cum	67.57			
1.5	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork)SSRBW: 2000	Cum	23.80			
1.6	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M20 (Including Formwork)SSRBW: 2000	Cum	52.50			
1.7	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications SSRBW: 2014	KG	2,160.49			

Total Item Price	
VAT (13.00%)	
Grand Total	