Bill of Quantities (BOQ)

Saptari Chetra no-1, Saptakoshi Na.Pa.9 ma Thapa Khang ko ghar dekhi odraha ward-8 ko shiva mandir samma RCC dhalan, Saptari Chetra no-1 Kanchanpur na.pa.-6 ma chandra nahar dekhi babadham hudai kalim ko ghar samma RCC dhalan.

IFB No.: 3370115012/IFB-01-083-84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for the loss or damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as described in Condition of Contract .	PS	1.00	54,000.00 Fifty-four thousand rupees only.	54,000.00 Fifty-four thousand rupees only.
PS.2	Provding, erection of project information board (size: 1.8mx1.2m) in flex print , in 50mm dia tubular steel post, all complete	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
PS.3	Provide, operate and maintain quality control laboratory including quality control engineer equipment, accessories and consumables for both field testing facilities and off site test with manpower along with transportation facility for employer as per specification as instructed by engineer.	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
	Total provisional sums				1,09,000.00 One lakh nine thousand rupees only.

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Construction of Embankment with Material obtained from Borrow pits. Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications.	cum	27.51			
1.2	Providing and laying Granular Sub-Base Material. By Mechanical means . Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications.	cum	223.56			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Scarifying Existing road Surface to a depth of 50 mm by Mechanical Means.Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications.	sqm	1,490.40			
1.4	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications.including formwork Grade M 20	cum.	223.56			
1.5	Providing and laying , fitting and placing un-coated reinforcement complete in Superstructure as per drawing and technical specification and Engineers instructions all complete.(SS-2014)	Kg	11,935.967			
1.6	Providing 6mm Plywood for the use of construction joint all complete as instructed by Engineer	sqm	37.26			

Total Item Price	
VAT (13.00%)	
Grand Total	