Bill of Quantities (BOQ)

Road Upgrading Works at Majuwa Gauripokhari, Chandrakot-8, Majuwa Bazaar Drainage and Road Upgradation Chandrakot 8, Settlement Development Program work at Rampur Surya Dangsing Chandrakot 8 Gulmi

IFB No.: 3470150015/UDBOP-NCB-083/84-04

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance premium for the work, plant and materials damage for contract work for the insurance of owner and consultant staff (named); Insurance Premium for construction equipments and machines; Insurance Premium for third party liability personal only	PS	1.00	28,442.12 Twenty-eight thousand four hundred forty-two rupees and twelve paisa only.	28,442.12 Twenty-eight thousand four hundred forty-two rupees and twelve paisa only.
PS.2	Material Tests	PS	1.00	32,544.00 Thirty-two thousand five hundred forty-four rupees only.	32,544.00 Thirty-two thousand five hundred forty-four rupees only.
PS.3	Supply and Place standard size sign board for Construction Information	PS	1.00	4,000.00 Four thousand rupees only.	4,000.00 Four thousand rupees only.
	Total provisional sums				64,986.12 Sixty-four thousand nine hundred eighty-six rupees and twelve paisa only.

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	cum	12.80			
1.2	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (mechanical means)	cum	231.85			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying of hand pack Stone soling with stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum	88.04			
1.4	Providing and laying plain Cement Concrete PCC(Grade M15) Including batching , mixing, transporting,placing,,compactiing,finishing,curing and formwork wherever required,complete in accordance with the approved drawings, DOR Standard Specifications and instructions of the Engineer	cum	78.10			
1.5	Providing and laying granular sub-base with Preparation of Subgrade on prepared surface, mixing at OMC, and compacting to achieve the desired density, all complete as per Technical Specifications. [SPEC. 1201]	cum	84.32			
1.6	Providing and laying Reinforcement Cement Concrete RCC(GradeM20)Including batching , mixing, transporting,placing, vibrating ,compactiing,finishing,curing and formwork wherever required,complete in accordance with the approved drawings, DOR Standard Spec	cum	113.50			
1.7	Laying of Polyethene Plastic over prepared Sub-base to cater for rigid pavement as per drawing and technical Specifications.	sqm	562.05			
1.8	Supplying,cutting,bending and fixing high yield deformed reinforcement steel including binding wire chairs spacers laps and all incidental works complete in accordance with the approved drawing DOR Standard Specifications and instructions of the Engineer	kg	3,708.90			
1.9	Providing and laying Plum concrete (Boulder mixed concrete)including formwork as per Drawing and Specifications 60% M 15(1:2:4) concrete and 40% Boulders/stones Mechanically .	cum	6.36			

Total Item Price	
VAT (13.00%)	
Grand Total	