Bill of Quantities (BOQ)

Pahelo gate dekhi sahuwatikar jane bato starounnati

IFB No.: 801054702/RAM/NCB/WORKS/04/2083-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance against damage of property and life during construction	PS	1.00	24,900.00 Twenty-four thousand nine hundred rupees only.	24,900.00 Twenty-four thousand nine hundred rupees only.
PS.2	Lab test of materials as directed by engineer or site in-charge	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				34,900.00 Thirty-four thousand nine hundred rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Information board as per the instruction of site incharge	No	1.00			
1.2	Drain excavation in Ordinary soil as per Drawing and Technical Specification including removal of stumps and other deleterous matter, all lift and leads as per Drawing and Instruction of the Engineer. By Mechanical Means	m^3	148.50			
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	m^3	29.70			
1.4	Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications	m^3	103.28			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Providing and laying of RCC (Grade M 15) in foundation & Super Structure all complete with fair finish Formwork as per Drawing and Technical Specifications	m^3	16.20			
1.6	Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (SS Clause 2014)	kg	1,537.60			
1.7	Providing and laying Brick Masonry Work in Cementmortar (cement:sand 1:4) in Foundation/Structure complete excluding pointing,plastering etc all complete as per Drawing and Technical Specifications	m^3	55.89			
1.8	Providing and applying plastering in Cement mortar (cement:sand1:4) on brick work in structure as per Drawing and Technical Specifications	sqm	162.00			
1.9	Construction of Subgrade and Earthen with approved Material obtained from borrowpits with all lifts and leads as per Drawingand Technical Specifications.	m^3	32.40			
1.10	Providing and laying granular sub-base on prepared surface,mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications	m^3	54.00			

Total Item Price	
VAT (13.00%)	
Grand Total	