Bill of Quantities (BOQ)

Yashok madan Aasharit piplebote bhulke sadak staronanti

IFB No.: KUMMAYAKRM/2083-084/KRM-NCB-04

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, Plants, materials,loss and damage to equipments, Contractor's workmen,employees and third party insurance against damage to other persond and property.	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
PS.2	Carry out additional tests for material and works as required and instructed by engineer.	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
PS.3	Provide and installation of project information board size 1.8 X 1.2 m along with iron posts including excavation ,concreting, backfilling all complete as per Specification.	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
	Total provisional sums				1,05,000.00 One lakh five thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Preparation of subgrade mentaining up to 15 cm depth soil levelling, providing all equipments, rolling fully by roller and all the job complete as per norms and specification or direction of site engineer.	Sqm	7,000.00			
1.2	Roadway Excavation in all types of Soil by Mechanical Means . Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. Unit = cum (For 360 cum)	Cum	552.75			
1.3	Providung and laying granular sub-base on prepared surface, mixing at OMC and compacting to achieved the desired density, complete as per Drawing and Technical Specification (for 300cum)	Cum	840.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Fabrication of gabion boxes including cutting, waving hexagonal 3 mm mesh size (100mmx120mm)mesh wire (Heavy Coated) of 10SWG., salvage wire 8SWG.	Sqm	846.00			
1.5	"Providing and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications. Unit = cum (For 10 cum)"	Cum	167.50			
1.6	500 mm dia HDPE Pipe for water cross drainage work per mtr wt = 55.084 kg	kg	2,478.78			
1.7	Chamber wall stone masonary 1:6 (cement sand) including providing material, mixing of mortar, laying of stone, curing and finishing all complete job.	Cum	13.94			

Total Item Price	
VAT (13.00%)	
Grand Total	