Bill of Quantities (BOQ)

Settlement Development work at Kulomuni Kumal Gau, Bagnashkali-01 and Road Upgrading Work at Dhrubghat Ring Road Tansen.-1, Palpa

IFB No.: 3470150015/UDBOP-NCB-083/84-09

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance premium for the work, plant and materials damage for contract work for the insurance of owner and consultant staff (named); Insurance Premium for construction equipments and machines; Insurance Premium for third party liability personal only	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.2	Material Tests	PS	1.00	8,136.00 Eight thousand one hundred thirty-six rupees only.	8,136.00 Eight thousand one hundred thirty-six rupees only.
PS.3	Supply and Place standard size sign board for Construction Information	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				35,136.00 Thirty-five thousand one hundred thirty-six rupees only.

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (mechanical means)	cum.	132.35			
1.2	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	cum.	44.10			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying of hand pack Stone soling with stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum.	62.53			
1.4	Providing and laying of PCC 1:2:4 (Grade M 15) in foundation complete as per Drawing and Technical Specifications	cum.	8.70			
1.5	Construction of stone masonry for Retaining walls/drains in 1:4 cement-sand mortar with 4" HDPE pipe weep hole including supply of materials, curing all complete.	cum.	134.43			
1.6	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications.	cum.	81.00			
1.7	Providing and laying Reinforcement Cement Concrete RCC(GradeM20)Including batching , mixing, transporting,placing, vibrating ,compactiing,finishing,curing and formwork wherever required,complete in accordance with the approved drawings, DOR Standard Specifications and instructions of the Engineer	cum.	51.35			
1.8	Supplying,cutting,bending and fixing high yield deformed reinforcement steel including binding wire chairs spacers laps and all incidental works complete in accordance with the approved drawing DOR Standard Specifications and instructions of the Engineer	Kg	1,786.50			

Total Item Price	
VAT (13.00%)	
Grand Total	