Bill of Quantities (BOQ)

Settlement Development work at Gaire Tole Dalit Basti, Satyawati-6 and Settlement Development work From Bhute Dhunga via SK Mode to Thamka Shivalaya Temple, Satyawati-6, Settle Conservation Program Jimirebot-Daudarekhola Johang Bidauri Satyawati-6 a

IFB No.: 3470150015/UDBOP-NCB-083/84-03

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance premium for the work, plant and materials damage for contract work for the insurance of owner and consultant staff (named); Insurance Premium for construction equipments and machines; Insurance Premium for third party liability personal only	PS	1.00	33,007.30 Thirty-three thousand seven rupees and thirty paisa only.	33,007.30 Thirty-three thousand seven rupees and thirty paisa only.
PS.2	Material Tests	PS	1.00	40,680.00 Forty thousand six hundred eighty rupees only.	40,680.00 Forty thousand six hundred eighty rupees only.
PS.3	Supply and Place standard size sign board for Construction Information	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
	Total provisional sums				78,687.30 Seventy-eight thousand six hundred eighty-seven rupees and thirty paisa only.

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	cum	204.47			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.2	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (mechanical means)	cum	333.99			
1.3	Providing and laying of hand pack Stone soling with stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum	192.48			
1.4	Providing and laying plain Cement Concrete PCC(Grade M15) Including batching , mixing, transporting,placing,,compactiing,finishing,curing and formwork wherever required,complete in accordance with the approved drawings, DOR Standard Specifications and instructions of the Engineer	cum	70.12			
1.5	Providing and laying Plum concrete (Boulder mixed concrete)including formwork as per Drawing and Specifications 60% M 15(1:2:4) concrete and 40% Boulders/stones Mechanically .	cum	56.71			
1.6	Providing and laying Reinforcement Cement Concrete RCC(GradeM20)Including batching , mixing, transporting,placing, vibrating ,compactiing,finishing,curing and formwork wherever required,complete in accordance with the approved drawings, DOR Standard Spec	cum	124.43			
1.7	Supplying,cutting,bending and fixing high yield deformed reinforcement steel including binding wire chairs spacers laps and all incidental works complete in accordance with the approved drawing DOR Standard Specifications and instructions of the Engineer	Kgs	3,874.69			
1.8	Construction of stone masonry for Retaining walls/drains in 1:4 cement-sand mortar with 4" HDP pipe weap hole including supply of materials, curing all complete.	Cum	64.70			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.9	"Providing and Pointing with cement mortar (1:3) on masonry work in structure as per Technical Specifications "	Sqm	64.10			

Total Item Price	
VAT (13.00%)	
Grand Total	