Bill of Quantities (BOQ)

Patalpani Chalne Malika Water supply Project Construction ward No 4 Jajarkot

IFB No.: 801066601/CM/NCB/WORKS/04/2083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance	PS	1.00	80,000.00 Eighty thousand rupees only.	80,000.00 Eighty thousand rupees only.
	Total provisional sums				80,000.00 Eighty thousand rupees only.

Construction work for water projects CPV: 45240000-1 - Construction work for water projects						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	E/W in excavation in All Type Soil	cum	898.38			
1.2	E/W in excavation in Boulder mix Soil	cum	224.60			
1.3	E/W in backfilling with All type soil	cum	786.08			
1.4	Laying and jointing of 50&63 mmØ HDPE pipes	rm	7,130.00			
1.5	Procurement of PE 100 Grade HDPE Pipe Size 63MM @ PN12.5	rm	3,220.00			
1.6	Procurement of PE 100 Grade HDPE Pipe size 50 mm @PN 16	rm	3,910.00			
1.7	Procurement of GI Pipe 2½ "	rm	260.00			
1.8	Procurement of GI Pipe 2 "	rm	90.00			
1.9	Procurement of GI flange Set 80mm	set	14.00			

Construction work for water projects CPV: 45240000-1 - Construction work for water projects						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.10	Procurement ofAir Valve 25mm	set	6.00			
1.11	Procurement of Gate Valve 65mm	no	1.00			

Total Item Price	
VAT (13.00%)	
Grand Total	