Bill of Quantities (BOQ)

Road and drainage management from Tamghas Bazaar (via Arjun Boarding Chowk and Sahutol) to Milan Chowk, Resunga-1, Gulmi and Road Upgrading at Budhichaur–Panikunta–Chhap–Tallo Bhitri, Resunga -8, Gulmi

IFB No.: 3470150015/UDBOP-NCB-083/84-20

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance premium for the work, plant and materials damage for contract work for the insurance of owner and consultant staff (named); Insurance Premium for construction equipments and machines; Insurance Premium for third party liability personal only	PS	1.00	26,160.00 Twenty-six thousand one hundred sixty rupees only.	26,160.00 Twenty-six thousand one hundred sixty rupees only.
PS.2	Material Tests	PS	1.00	10,170.00 Ten thousand one hundred seventy rupees only.	10,170.00 Ten thousand one hundred seventy rupees only.
PS.3	Supply and Place standard size sign board for Construction Information	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				38,330.00 Thirty-eight thousand three hundred thirty rupees only.

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cum	140.70			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.2	Dismentaling of existing structures like Stone masonary drain and other structures comporising of masonary cement concerte the dismentalled materials ,disposal of underviceable material and stacking the serviceable material with all lift and lead of 1000m.(i) cement concete masonary wall	Cum	28.94			
1.3	Providing and laying of hand pack Stone soling with stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum	47.10			
1.4	Providing and laying plain Cement Concrete PCC(Grade M15) Including batching , mixing, transporting,placing,,compactiing,finishing,curing and formwork wherever required,complete in accordance with the approved drawings, DOR Standard Specifications and instructions of the Engineer	Cum	14.96			
1.5	Construction of stone masonry for Retaining walls/drains in 1:4 cement-sand mortar with 4" HDP pipe weap hole including supply of materials, curing all complete.	Cum	18.68			
1.6	Providing and Pointing with cement mortar (1:3) on masonry work in structure as per Technical Specifications	sqm	25.00			
1.7	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications 60% M 15 concrete and 40% Boulders/stones Mechanically with formwork .	Cum	6.60			
1.8	Providing and laying Reinforcement Cement Concrete RCC(Grade M20) in with formwork Including batching , mixing, transporting,placing,vibrating, compactiing,finishing,curing ,complete as per approved drawing,technical Specifications and instructions of the Engineer	Cum	59.61			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.9	Supplying,cutting,bending and fixing high yield deformed reinforcement steel including binding wire chairs spacers laps and all incidental works complete in accordance with the approved drawing DOR Standard Specifications and instructions of the Engineer	kg	3,510.53			

Total Item Price	
VAT (13.00%)	
Grand Total	