Bill of Quantities (BOQ)

Combined Package for the Construction of Siddhako Than – Syapari – Dandatole Mororbato and Dandatole – Jalkimi – Kshamamai Mandir Motorbato, Jaljala -4, Parbat

IFB No.: 3370142014/IDOP/NCB/W/10/2083-84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance of works, plants, materials, loss and damage to equipment, contractor's workmen and employees and third party insurance against damage to other persons and property as per specifications and instructions of the engineer (GCC 19)	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.2	Relocation of services and minor infrastructures as per specification and instructions of the engineer (SSRBW 105)	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
	Total provisional sums				50,000.00 Fifty thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Earthwork in excavation of foundation of structures in all types of soil an rock by mechanical means, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 900, 907)	m^3	488.93			
1.2	Providing and laying of hand packed stone soling with 150 to 200 mm thick stones and packing with smaller stones on prepared surface as per drawings, technical specifications and instructions of the engineer (SSRBW 1000, 3111)	m^3	50.59			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying of M15 PCC including formworks, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2000)	m^3	21.18			
1.4	Providing and laying plum concrete including formworks (60% machine-mixed M15 concrete and 40% boulders / stone) including providing weep holes (not required in drain), all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2400, 2421)	m^3	285.79			
1.5	Providing mechanically woven double twisted gabion crates / mattresses including rolling, cutting and with lacing wire and binding wire, assembling them, placing in position including stretching, forming compartments, tying the sides and diaphragms with binding wire in each mesh, tying with bracing wires and tie wires and tying down the lid, providing and filling stone / boulder in gabion boxes / mattress etc. including dressing, bedding, bonding, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2400, 2402)	m^3	76.50			
1.6	Providing, laying and fixing of geo-textile, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2400, 2404)	m^2	51.00			
1.7	Providing and laying reinforced cement concrete 600 mm internal diameter NP3 flush jointed Hume pipe for culverts including fixing with cement mortar 1:2, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 700, SSRBW 701)	r.m	7.50			
1.8	Providing and laying of M20 concrete for RCC including formworks, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2000)	m^3	7.00			
1.9	Providing and laying, fitting and placing HYSD reinforcement, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2000, 2014)	kg	254.51			

Total Item Price	
VAT (13.00%)	
Grand Total	