Bill of Quantities (BOQ)

Gumasta Gauma Kalopatre

IFB No.: 801055804/BMO/NCB/W/2083-84/5

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Supply, deliver, and install a standard-size project information board as per approved specifications. Provide and maintain all required insurances for the project duration, including Insurance of Works, Equipment, Contractor's Workmen/Employees, and Third-Party Liability against damage to persons and property. Carry out additional tests for materials and works as required and instructed by the Engineer. Provide a Provisional Sum for the operational and logistical expenses of the project management team (Project Manager, Site In-charge, Site Supervisor, and Monitoring Committee). This sum strictly covers actual fuel and oil for site visits, vehicle maintenance, and miscellaneous administrative or meeting expenses. It shall be expended or deleted at the sole discretion of the Engineer. Reimbursement will be made on a remeasurement basis against genuine tax invoices and logbooks, with zero contractor profit or markup allowed."	PS	1.00	35,496.95 Thirty-five thousand four hundred ninety-six rupees and ninety-five paisa only.	35,496.95 Thirty-five thousand four hundred ninety-six rupees and ninety-five paisa only.
	Total provisional sums				35,496.95 Thirty-five thousand four hundred ninety-six rupees and ninety-five paisa only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of light jungle (less than 15 number per 100 sqm, Unit = sqm, (for 10,000 sqm))	Sqm	306.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.2	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications.(SS 1003)	Sqm	918.00			
1.3	Providing and laying granular sub-base on prepared surface,mixing at OMC,and compacting to achieve the desire density,complete as per drawing and Technical Specification.(A) By Mechanical Means.. [SS 1201]	cum	91.80			
1.4	Crusher Run Macadam Base Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing , watering and compacting to form a layer of Base course as per Drawing and Technical Specifications.[SS 1204]	cum	137.70			
1.5	Providing and applying prime coat with Hot Bitumen(including cutter) on prepared surface of granular base including cleaning of road surface and spraying at specified rate by manual means as per Technical Specification .(By Mechanical means)[SS 1303]	Lit.	619.65			
1.6	Providing and applying tack coat with hot Bitumen at specified rate on the prepared non-bituminous surfaces including cleaning as per Technical Speciation . (By Mechanical means) [SS 1302]	Lit.	367.20			
1.7	Providing and laying Asphalt concrete Grading -II (Nominal Size) using crushed aggregates of specified grading, premixed with bituminous binder and filler as per Drawing and Technical Specifications. [SS 1309]	cum	24.48			
1.8	Providing and laying granular sub-base on prepared surface for shoulder,mixing ,(loose gravel) manually,complete as per drawing and Technical Specification.(A) By Manual Means.. [SS 1201]	cum	61.20			

Total Item Price	
VAT (13.00%)	
Grand Total	