Bill of Quantities (BOQ)

Shree Kanti Ma.Vi. and Thakali Samaj Truss Repair and Maintenance Work

IFB No.: 801054801/10/BSMC/IDD/WORKS/NCB-083-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Supply and placing project information board/ hoarding boards, carryout Extra lab test (If necessary) and photography of work, event and materials as per requirement and instruction, all complete	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.2	Insurance for the loss or damage to works, plants, materials, equipment, property and personal injury or death including Employer, Contractor and third parties as per conditions of contract.	PS	1.00	30,000.00 Thirty thousand rupees only.	30,000.00 Thirty thousand rupees only.
PS.3	Provisional Sum for `Minor repairs at existing Roof & specially for Electrification work at Thakali samaj Truss (Open Hall)	PS	1.00	1,50,000.00 One lakh fifty thousand rupees only.	1,50,000.00 One lakh fifty thousand rupees only.
PS.4	Provisional Sum for `Minor repairs at existing Roof & specially for Electrification work at Thakali samaj Truss (Open Hall)	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
	Total provisional sums				2,15,000.00 Two lakh fifteen thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing & laying (60*60) Vertified floor tiles in 1:4 cement sand mortar in perfect lines & level finishing the joint with white cement with or without pigments where necessary(Including preparation of floor by Dismentaling & Removing Existing Concrete floor As per Requirement) all complete as per design drawings, patterns, specifications and instruction of the site engineer:	sqm	479.96			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.2	Supplying and Painting single coat weather proof paint (Apex or equivalent) on outer wall surfaces with approved colour and proper finishing , work all complete as per specification and approval of site Engineer.	sqm	2,700.00			
1.3	Fabricating supplying and fixing of M/S Frame Work including proper priming and Double coat Enamel painting all complete works .	kg	75.00			
1.4	Provnding & Fixing of .5 mm thk NS Quality or Equivalent C.G.I. sheet roof covering at Truss roof.	sqm	69.25			
1.5	Providing and Fixing PVC Ceiling with 8mm thickness pannels Under CGI sheet roof including all necessary Supports and FixuresWith necessary pattern of decoration as par Reuirement.	sqm	539.00			
1.6	Supplying and Painting Double Coat. enamel paint (Apex or equivalent) on metalled surfaces with approved colour and proper finishing , including applying of one coat primer work all complete as per specification and approval of site Engineer.	sqm	660.00			

Total Item Price	
VAT (13.00%)	
Grand Total	