Bardibas Municipality
Office of Muncipal Excecutive
Bardibas, Mahottari
Madhesh Province, Nepal

Bill Of Quantities

Project Name :- जलेश्वर राजमार्गबाट तल भब्सी हुँदै चल्की हुँदै वरटोल सम्म कालोपत्रे
Project Location: बर्दिबास नगरपालिका-८, १२, १३ **F/Y:- 2083/084**

Item No.	Description of work	Unit	Quantity	Rate		Amount	Remarks
				Figures	Words		
1	**Povisional Sum**						
1.1	Insurance for the los of or damage to works,plants, materials, equipments, property and personal injury or death including employer,contractor and Third parties ll complete (Clause 14 GCC/SCC)	PS	1.00				
1.2	Provide, operate and maintain Quality control laboratory including equipment, accessories and consumables for both field testing facilities and off-site test as per Contract Document (SS/SP-502, 511). At the end of project all the equipment and accessories shall be handed over to client.	PS	1.00				
1.3	Engineer's Facilities: Establishment and maintenance of office and site camp etc. and providing furniture and other facilities as directed by the Enginer.	PS	1.00				
Total Part 1: Carried to Summary							
2	**General item**						
2.1	Provide and Install Project Signboards. (SS/SP-108)	Nos.	2.00				
Total Part 2: Carried to Summary							
3	**Pavement Work**						
3.1	Preperation of Sub-Grade by Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material by Mechanical Means with all lifts and leads as per Drawing and Technical Specifications. (SS/SP-1003)	m^2	18633.87				
3.2	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by Mechanical Means, all complete as per Drawing and Technical Specifications. (SS/SP-1201)	m^3	2329.23				
3.3	Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing, watering and compacting to form a layer of Base course, all complete as per Drawing and Technical Specifications. (SS/SP-1202)	m^3	2795.08				
3.4	Providing and applying prime coat with Hot Bitumen (including cutter) on prepared surface of granular base including cleaning of road surface and spraying by mechanical means as per Technical Specification. (SS-1301,1302)	Lit	16770.49				
3.5	Providing and applying tack coat with hot Bitumen at specified rate on the prepared non-bituminous surfaces including cleaning of road surface and spraying by mechanical means as per Technical Speciations. (SS/SP-1301,1302)	Lit	8784.54				
3.6	Providing and Laying open graded premix carpet, composed of 13.2 mm to 5.6 mm aggregates as wearing coarse on a previously prepared base by mechanically means as per drawing and technical specifications. (1307,1308)	m^3	585.64				
3.7	Providing and laying seal coat sealing the voids in a bituminous surface as per Drawing and Technical Specifications. (SS/SP-1310)	m^2	14640.91				
Total Part 3: Carried to Summary							
Total Sum (Part 2+3) without PS							
Sub Total with PS (Part 1+2+3)							
13% VAT without PS							
Grand Total with VAT and PS							

Prepared By: Checked By: Approved By: