Bill of Quantities (BOQ)

जलेश्वर राजमार्गबाट तल भब्सी हुँदै चल्की हुँदै वरटोल सम्म कालोपत्रे |

IFB No.: 80218403300/BM/NCB/WORKS/083/84-01

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the los of or damage to works,plants, materials, equipments, property and personal injury or death including employer,contractor and Third parties ll complete (Clause 14 GCC/SCC)	PS	1.00	80,000.00 Eighty thousand rupees only.	80,000.00 Eighty thousand rupees only.
PS.2	Provide, operate and maintain Quality control laboratory including equipment, accessories and consumables for both field testing facilities and off-site test as per Contract Document (SS/SP-502, 511). At the end of project all the equipment and accessories shall be handed over to client.	PS	1.00	1,70,000.00 One lakh seventy thousand rupees only.	1,70,000.00 One lakh seventy thousand rupees only.
PS.3	Engineer's Facilities: Establishment and maintenance of office and site camp etc. and providing furniture and other facilities as directed by the Enginer.	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
	Total provisional sums				3,00,000.00 Three lakh rupees only.

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Provide and Install Project Signboards. (SS/SP-108)	Nos	2.00			
1.3	Preperation of Sub-Grade by Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material by Mechanical Means with all lifts and leads as per Drawing and Technical Specifications. (SS/SP-1003)	m2	18,633.87			
1.4	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by Mechanical Means, all complete as per Drawing and Technical Specifications. (SS/SP-1201)	M3	2,329.23			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.6	Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing, watering and compacting to form a layer of Base course, all complete as per Drawing and Technical Specifications. (SS/SP-1202)	M3	2,795.08			
1.5	Providing and applying prime coat with Hot Bitumen (including cutter) on prepared surface of granular base including cleaning of road surface and spraying by mechanical means as per Technical Specification. (SS-1301,1302)	Ltr	16,770.49			
1.7	Providing and applying tack coat with hot Bitumen at specified rate on the prepared non-bituminous surfaces including cleaning of road surface and spraying by mechanical means as per Technical Speciations. (SS/SP-1301,1302)	Ltr	8,784.540017			
1.8	Providing and Laying open graded premix carpet, composed of 13.2 mm to 5.6 mm aggregates as wearing coarse on a previously prepared base by mechanically means as per drawing and technical specifications. (1307,1308)	M3	585.64			
1.9	Providing and laying seal coat sealing the voids in a bituminous surface as per Drawing and Technical Specifications. (SS/SP-1310)	M2	14,640.91			

Total Item Price	
VAT (13.00%)	
Grand Total	