Bill of Quantities (BOQ)

Upgrading of Motorable Road from Rautala to Chiura Panchadana to Kafalpani, Bangad Kupinde Municipality, Salyan

IFB No.: 3370160016/02/IDO/SLN/W/NCB/03/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss of damage to works, plant, material, equipment property and personnel injury or death, including third party insurance . [GCC:19.1]	PS	1.00	85,000.00 Eighty-five thousand rupees only.	85,000.00 Eighty-five thousand rupees only.
PS.2	Providing and installation of Project Signboards with size of 1.8 x1.2m as per specification and instruction of Engineer. [SSRBW 110]	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				95,000.00 Ninety-five thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	cum	524.71			
1.2	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of light jungle (less than 15 number per 100 sqm, Unit = sqm, (for 10,000 sqm))	sqm	515.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per Drawing and Technical Specifications. [SSRBW 908]	cum	311.05			
1.4	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. (Old Norms)	cum	77.20			
1.5	"Providing and placing machine mixed cement concrete of M15/40 for the foundation and footing etc. including formwork, compaction,curing,testing etc all complete as per specification "	cum	69.33			
1.6	Providing and laying of Plain Cement Concrete M10 in foundation complete as per Drawing and Technical Specifications.	cum	1.64			
1.7	"Providing and laying of PCC (Grade M 25/40) in foundation complete as per Drawing and Technical Specifications "	cum	103.00			
1.8	"Providing and laying Random Rubble Stone Masonry work in cement mortar 1:4 in structure including weep holes complete as per Drawing and Technical Specification. [SSRBW 2607 & 3109] "	cum	398.14			
1.9	Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (SS Clause 2014)	MT	3.94			
1.10	Providing and Laying RCC 900mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	RM	40.00			

Total Item Price	
VAT (13.00%)	
Grand Total	