Bill of Quantities (BOQ)

Upgrading and Construction work of Nepal Red Cross Society, Ward No. 13

IFB No.: 801054805/SNP/NCB-15/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Providing and installation of Project Signboards,Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property, Carry out additional tests for material and works,and services,Dismantling of the existing structures (Septic Tank),etc. as instructed by the Engineer and other necessary unforeseen works as per approved Norms and Technical Specifications.	PS	1.00	60,000.00 Sixty thousand rupees only.	60,000.00 Sixty thousand rupees only.
	Total provisional sums				60,000.00 Sixty thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Clearing the site of all the vegetation, roots and other unuseful materials including excavation of top soil to a depth of 15 cm, removing bushes, trees and leveling the Site for stacking the useful items in specified space and disposing other item before commencing the construction work as per instruction of the site engineer all complete including layout of buildings, roads and ancillary services.	Sq.m	164.615556			
1.2	Chimney Made 1st Class Brick work (1:4) in above Ground floor in cement sand mortar with approved quality bricks in perfect line & level with necessary scaffolding including wetting the bricks, properly packing the joints & curing the works with all complete,as per specifications, drawings and instructions of the site engineer,all complete.	Cu.m	6.310975			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing, laying, compacting and curing M20 (1:1.5:3) plain cement concrete(RMC) works with cement sand and stone ballast 20mm down finishing to approved level, line and dimensions all complete as per specifications, drawings and instructions of the site engineer, all complete.	Cu.m	33.716201			
1.4	Providing, laying, compacting and curing M20 (1:1.5:3) plain cement concrete works with cement sand and stone ballast 20mm down finishing to approved level, line and dimensions all complete as per specifications, drawings and instructions of the site engineer, all complete.	Cu.m	6.387804			
1.5	Steel Reinforcement work including straightening, cleaning, cutting, bending, binding wire & fixing in position as per drawing, bar bending schedule for foundation,column,all beam, wall, stair, slab in all R.C.C. works as per specification, drawing & instruction of site engineer,all complete.	K.g	6,933.392979			
1.6	Form work for column including supply and selection of materials fixing, nailing according to drawings, placing separa- tors, dismantling forms and hauling upto 30 m distance	Sq.m	86.40			
1.7	Centering and shuttering for Beam other RCC work including all necessary propping, scaffolding,staging, supporting, dismantling and clearing from the site, including shuttering all complete as per design drawings, specifications and instruction of the site engineer .	Sq.m	105.639634			
1.8	Centering and shuttering for Slab other RCC work including all necessary propping, scaffolding,staging, supporting, dismantling and clearing from the site, including shuttering all complete as per design drawings, specifications and instruction of the site engineer .	Sq.m	203.448981			
1.9	2x3/20 Pvc Cu. Wire for light and fan point 1/2" HDPE polythene Pipe with accessories, screw, Tape, grips, Circular box etc all complete.	Point.	20.00			

Total Item Price	
VAT (13.00%)	
Grand Total	