Bill of Quantities (BOQ)

Upgrading of Road from Bajhgaau Ma.Vi. To Aadharbhut Swathya Kendra,Chulachuli Rural Municipality-05,Ilam

IFB No.: 3370103011/IDOILAM/NCB/W/04/83/84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for loss or damage to works, plant, material, equipment, property and personnel injury or death and third party as per contract data and technical specifiation (Cl. 19 of CoC)	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
PS.2	Carrying out laboratory and field tests on materials and completed works, as required and as directed by the Engineer, including all necessary arrangements and incidental works, complete.	PS	1.00	40,000.00 Forty thousand rupees only.	40,000.00 Forty thousand rupees only.
PS.3	Providing, writing and installation of the project information board as per the Standard Specifications and approved drawings and as instructed by the Engineer.	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				62,000.00 Sixty-two thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Preparation of subgrade by compacting original ground supporting sub-grade, loosening of the ground upto a level of 150 mm below the sub-grade level, watered, graded and compacted in layers as per drawwings and technical specifications. [Spec. cl. No: 1003,1005]	Sqm	904.50			
1.2	Providing,laying, spreading, levelling, watering of granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, all complete as per Drawing ,Technical Specifications and Engineer's Instructions.[Spec. cl. No: 1201]	Cum	152.76			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing, laying, levelling Crusher Run Macadam on a prepared surface, spreading and mixing , watering and compacting to form a layer of base course to achieve desired density as per Drawing , Technical Specifications and Engineer's Instruction.[Spec. cl. No: 1204]	Cum	120.60			
1.4	Providing and applying prime coat with hot bitumen MC 30/70 (including cutter)on prepared surface of granular base including cleaning, brooming, brushing of road surface and spraying at specified rate by mechanical means as per Technical specification. [Spec. cl. No: 1302,1302]	Ltr	723.60			
1.5	Providing and applying tack coat with hot Bitumen at specified rate on the prepared non-bituminous surfaces including cleaning, brushing, brooming etc. all complete as per Technical Speciation and Engineer's Instruction. [Spec. cl. No: 1302]	Ltr	402.00			
1.6	Providing and laying Bituminous concrete/ Asphalt concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler all complete as per Drawing and Technical Specifications and Engineer's instruction.[Spec. cl. No: 1309]	Cum	32.16			

Total Item Price	
VAT (13.00%)	
Grand Total	