Bill of Quantities (BOQ)

Nepal Chok dekhi Bhadadihawa Sadak Staronnati, Banganga Na Pa 11

IFB No.: 3370149015/02/RIDOKAP/10134/SQ/083-84/24

Construction work **CPV: 45000000-7 - Construction work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Supply, place and maintain standard size 0.9 x 1.2 m sign board for Project information and Prepare and submit progress report/Final Report with Color prints in A4 size paper color photo and video.[110]	No.	1.00			
1.2	Loosening, levelling, and compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve dry density as per Drawing and Technical Specification (compacting orginal ground supporting embankment) [1003,1005]	Sqm	3,666.60			
1.3	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.(1201)	Cum	549.99			

Total Item Price	
VAT (13.00%)	
Grand Total	