Bill of Quantities (BOQ)

Upgrading Works of Sukrabare Bazar Road

IFB No.: 801010307/MJRM/NCB/WORKS /083/084-07

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the damage and loss of works,plants,and vehicles;personal injuries,death of labours,Employees and other third party Insurance	PS	1.00	17,000.00 Seventeen thousand rupees only.	17,000.00 Seventeen thousand rupees only.
PS.2	Construction materials test as directed by site Engineer	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
PS.3	1500 x 1200 mm Size Site information board as specified	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				39,000.00 Thirty-nine thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications.	cum	56.16			
1.2	Stone pitching/ Soling work on the prepared bedding with filling of voids by granular material/ spalls as per direction of the engineer all complete	cum	2.77			
1.3	Stone pitching/ Soling work on the prepared bedding with filling of voids by granular material/ spalls as per direction of the engineer all complete Type 1	cum	15.90			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.8	"Providing, Preparing and Installing form work including necessary supports and removing after completion for precast element/ all type of structures. Class F3 Finish I) Square/ Rectangular/ Circular Sections/ Verticle surfaces a) Using Timber & Plywood"	sqm	42.23			
1.5	Providing and laying, fitting and placing HYSD/ Mild Steel bar reinforcement in sub-structure complete as per Drawing and Technical Specifications	k.G	2,706.70			
1.6	Providing and laying of Plain/ Reinforced Cement Concrete (RCC Grade M20) in Foundation complete as per Drawing and Technical Specifications.	cum	68.34			
1.7	"Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications A. 60% M 15 concrete and 40% boulders/ stones (Using Mechanical Aids)"	cum	11.25			

Total Item Price	
VAT (13.00%)	
Grand Total	