Bill of Quantities (BOQ)

Upgrading Works of Ruluk Pyang ma bi Panchami Gumba Danda Thumke Road

IFB No.: 801010307/MJRM/NCB/WORKS /083/084-03

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the damage and loss of works,plants,and vehicles;personal injuries,death of labours,Employees and other third party Insurance	PS	1.00	75,000.00 Seventy-five thousand rupees only.	75,000.00 Seventy-five thousand rupees only.
PS.2	Construction materials test as directed by site Engineer	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.3	1500 x 1200 mm Size Site information board as specified	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
	Total provisional sums				90,000.00 Ninety thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (MECHANICAL MEANS)	cum	1,363.33			
1.2	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical	cum	105.00			
1.3	Roadway Excavation in ordinary rock as per Drawing and Technical specification, including all lift and lead as per Drawing and instruction of the Engineer. (Mechanical Means)	cum	65.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Stone pitching/ Soling work on the prepared bedding with filling of voids by granular material/ spalls as per direction of the engineer all complete	cum	1,480.83			
1.5	"Providing mechanically woven double twisted crates/ mattress including rolling, cutting and with lacing wire and binding wire including assembling mechanical woven Gabion boxes /mattresses, placing in position including stretching; forming compartments; tying the sides and diaphragms with binding wire in each mesh; tying with bracing wires and tie wires; and tying down the lid complete as per specification Providing and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications.Type 1	cum	54.00			
1.6	Providing and laying of a geotextile filter between pitching and embankment slopes as per Drawing and Technical Specifications.	sqm	36.00			

Total Item Price	
VAT (13.00%)	
Grand Total	