Bill of Quantities (BOQ)

Construction of Sanibheri Siksha Campus Building

IFB No.: 1123/SANIC/01/NCB/W/2083-084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Provisional Sum(lab test ,electric fiitngs ,sanitary and other miscellaneous items)	PS	1.00	4,00,000.00 Four lakh rupees only.	4,00,000.00 Four lakh rupees only.
	Total provisional sums				4,00,000.00 Four lakh rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	P.C.C. (1:1½:3) for R.C.C. work in slab, beam etc (Riverbed)	m3	86.75			
1.2	Torsteel reinforcement bar for R.C.C. work with cutting, bending, binding & laying with all complete.	kg	8,611.25			
1.3	First class chiminey brick masonry work in (1:4) cement sand mortar	m3	82.41			
1.4	Form work shuttering & centering with Bamboo (prop), Local wood Planks for slab ,Beam, Column etc	m2	855.01			
1.5	12.5mm thick Plastering work(1:4)	m2	806.49			
1.6	Two coat weather proof painting work without primer coat.	m2	806.49			
1.7	Local hard wood works for chaukhats with all complete.	m3	1.69			
1.8	38 x100mm thick Local Hard wood frame with 12 mm thick water proof plywood pannelled & one side 4 mm thick Teak plywood pannelled shutter fixing with all comolete. Size of	m2	25.37			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.9	Supplying & fixing work of 50 mm Ø stainless steel pipe post @ 2.0 mtr , 50 mm Ø stainless steel pipe hand rail with three rows 25 mm Ø stainless steel pipe in between ground & hand rail.	rm	50.00			

Total Item Price	
VAT (13.00%)	
Grand Total	