## Bill of Quantities (BOQ)

### Odari Coverd Hall dekhi Purva Dakshin jaane Adhuro Krishi Sadak Staronnati, Banganga 11

IFB No.: 3370149015/02/RIDOKAP/10134/SQ/083-84/22

| **Construction work**<br>**CPV: 45000000-7 - Construction work** | | | | | | |
|---|---|---|---|---|---|---|
| **SL. No.** | **Item Description** | **Unit** | **Quantity** | **Bidder's Rate (NPR)** | **Bidder's Rate (in words)** | **Total Amount (NPR)** |
| 1.1 | Supply, place and maintain standard size 0.9 x 1.2 m sign board for Project information and Prepare and submit progress report/Final Report with Color prints in A4 size paper color photo and video.[110] | No. | 1.00 | | | |
| 1.2 | Providing, laying, spreading, watering and compacting embankment with borrow material in layers not exceeding 150mm including haulage as per drawing and Technical Specifications. ( Mechanical Means)[909,910] | Cum | 249.90 | | | |
| 1.3 | Loosening, levelling, and compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve dry density as per Drawing and Technical Specification ( compacting orginal ground supporting embankment) [1003,1005] | Sqm | 1,485.00 | | | |
| 1.4 | Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.(1201) | Cum | 222.75 | | | |

| | |
|---|---|
| **Total Item Price** | |
| VAT (13.00%) | |
| **Grand Total** | |