Bill of Quantities (BOQ)

Dakshin Tol dekhi Dhaireni Dada tathaa Gaudicho Jodne Sadak, Banganga Na Pa 7

IFB No.: 3370149015/02/RIDOKAP/10134/SQ/083-84/16

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Supply, place and maintain standard size 0.9 x 1.2 m sign board for Project information and Prepare and submit progress report/Final Report with Color prints in A4 size paper color photo and video.[110]	No.	1.00			
1.2	Scarifying the existing Bituminious road surface by Mechanical means to a depth of 50 mm and disposal of scarified material with all lifts and leads within Right of Way as per Drawing and Technical Specification.[1003]	Cum	400.00			
1.3	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cum	3.90			
1.4	Providing and Laying RCC 450mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Rm	7.50			
1.5	Loosening, levelling, and compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve dry density as per Drawing and Technical Specification (compacting orginal ground supporting embankment) [1003,1005]	Sqm	638.55			
1.6	Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing, watering and compacting to form a layer of base course as per Drawing and technical Specifications.[1204]	Cum	95.78			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.7	Providing and Applying Prime coat with hot bitumen (including cutter) on prepared surface of granular base including cleaning of road surface and spraying at specified rate as per the Technical Specification. [1302]Engineer.	Lit	574.70			
1.8	Providing and Applying Tack coat with hot bitumen at specified rate on the prepared surfaces including cleaning as per the Technical Specification. [1302]	Lit	290.25			
1.9	Providing and laying close graded premix surfacing material (mechanical means) composed of 13.2 mm to 0.09 mm aggregates using bitumen as wearing course on a previously prepared base including mixing in a suitable plant as per the Technical Specification and Drawings. [1310]	Cum	11.61			

Total Item Price	
VAT (13.00%)	
Grand Total	