Bill of Quantities (BOQ)

Devdaha tal samrachaan,Charpala pratikshalaya Dekhi Panschim Jane Sadak,Sunwal-07.

IFB No.: 80547403/17.SUN/NCB/2083/84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss of damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as per Contract Document	PS	1.00	7,500.00 Seven thousand five hundred rupees only.	7,500.00 Seven thousand five hundred rupees only.
PS.2	Necessary Lab Test Work for official purpose.(Regular reports for Quality Assurance of work done shall be under Contractor responsibility)	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
PS.3	Supply & Installation of Project Information boards as per instructed by site engineer.	LS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
PS.4	Other Unseen Miscellenous Works as per approval. (Work Shall be done only on approval of the workorder by client as per approved norms and the payment of this item will be done according to submitted original copy ofrelated invoices)	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				39,500.00 Thirty-nine thousand five hundred rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Scarifying the existing road surface by mechanical means to a depth of 50 mm and disposal of scarified material with all lifts and leads as per Drawing and Technical Specification.	Sqm	390.50			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.2	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cum	23.92			
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones on prepared surface as per Drawing and Technical Specifications.	Cum	46.21			
1.4	Providing and laying of PCC (Grade M 10) in foundation all complete with fair finish Formwork as per Drawing and Technical Specifications	Cum	8.48			
1.5	Providing and laying of RCC (Grade M 20) in foundation & Super Structure all complete with fair finish Formwork as per Drawing and Technical Specifications	Cum	42.60			
1.6	Providing and laying, fitting and placing HYSD bar reinforcement in foundation & Super Structure complete as per Drawing and Technical Specifications (SS Clause 2014)	Kg	1,136.16			
1.7	Providing and laying Brick Masonry Work in Cement mortar (cement:sand 1:6) in Foundation/Structure complete excluding pointing, plastering etc all complete as per Drawing and Technical Specifications	Cum	40.46			
1.8	Heavy Coated Gabion wire chain link fencing with mesh size 3"x3" 10 gauge	Cum	361.35			
1.9	MS Pipe Work with one coat primer and enamel painting as per drawing and instruction of site engineer	Sqm	532.54			
1.10	Providing and laying loose granular sub-base on prepared surface, without compaction by mechanical means, complete as per Drawing and Technical Specifications.	Kg	10.65			

Total Item Price	
VAT (13.00%)	
Grand Total	